




VIBRATION MANAGEMENT CORPORATION

3532-A EAST TC JESTER , BROOKWOOD BUSINESS PARK , HOUSTON , TEXAS 77018 , U.S.A

INTERNET ADDRESS: www.vimco.biz



N.T.S.

NOTES

1. Isolators have a min. operating Kx/Ky ratio of 1.0
2. Springs have 50% additional travel to solid beyond rated load.
3. Isolators should be selected in the range of -30% to +25% of rated load.
4. Consult spring chart for isolator performance data.

ISOLATOR MODEL	RATED LOAD (lbs)	SOLID LOAD (lbs)
OSM-2-181	172	260
OSM-2-182	266	400
OSM-2-183	360	540
OSM-2-184	532	800
OSM-2-185	972	1460
OSM-2-186	1426	2140
OSM-2-187	1852	2780
OSM-2-181-199	1186	1780
OSM-2-182-199	1266	1900
OSM-2-183-199	1366	2050
OSM-2-184-199	1566	2350
OSM-2-185-199	1866	2800
OSM-2-186-199	2466	3700
OSM-2-187-199	2920	4380

FEATURES

- * Welded construction
- * Anti-skid elastomeric acoustical pad
- * Built-in leveling device
- * Mounting holes furnished as standard
- * Hot dip galvanized finish
- * High deflection, low natural frequency
- * Spring elements color-coded for easy field verification

Notes / Remarks :

Project :
Client :
Consultant :
Representative :

Title :

OSM-2
Free-standing Spring Mount
Welded Construction
(3" deflection)

Drawing no.

S-2050.22

Rev. 0